

Republic of the Philippines KALINGA STATE UNIVERSITY Bulanao, Tabuk City, Kalinga

PROJECT: REPAIR AND MAINTENMANCE (ROTC BLDG.) LOCATION: KSU Bulanao Campus, Tabuk City, Kalinga

TEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
1003 (1) a2	CEILING (Fiber Cement Board)	15.75	sq.m	Covers the replacement of the ROTC overall porch ceiling &
	OEIENO (Fiber Centent Board)	10.70	5q.111	portion of outside damage ceiling
				materials as follows Good Lumber (2" x 3" x 12")
				CWN (Assorted)
				4.5 mm Ficomboard (Fiber Cement Board)
				Ficomboard Nail
1716 (29)a	PAINTING WORKS (CONCRETE STRUCTURES)	104.28	sq.m	Covers the repainting of the 2 porch posts, inside concrete walls of the two (2) Office and ROTC outside walls except the rear walls.
				materials as follows
				Flat white Latex (1st Coat)
				Final Paint(2nd coat and 3rd coat-verify paint color)
				Masonry Neutralizer
				Masonry putty
				Sand paper #200
				Rollerbrush with pan
				Paint Brush x 100
				Paint Brush x 75
				Paint Brush x 50
				Roller brush foam
				Paint Thinner
				Covers the re-painting of the interior walls of the ROTC building
1032 (1) b	PAINTING WORKS (WOOD & FIBER CEMENT BOARD)	276.34	sq.m	(which includes all rooms, overall porch ceiling & portion of outside damage ceiling)
				materials as follows
				Flat white Latex (1st Coat)
				Final Paint(2nd coat and 3rd coat-verify paint color)
				Sand Paper # 200
				Plasolux Glazing Putty
				Paint Thinner
				Roller Brush Medium Size foam
				Roller Paint Brush M/S w/ pan
				Paint Brush x 100
				Paint Brush x 75
				Paint Brush x 50
				Enamel Choco Brown
1013 (1)	CORRUGATED METAL ROOFING	20.00	sq.m	Covers the Replacement of 2 damage corrugated roofing, application of vulcaseal to roofing w/ holes and installation of
				gutter with lumber support materials as follows
				ROOFING
				Gauge 26 GI Sheet (From Techvoc Salvage Materials)
				CWN (Assorted)
				Roofing Sealant
				GUTTER
				Gauge 24 (Gutter)
				Good Lumber (1" x 6" x 6") (Gutter Support)
				Gutter Bracket
1001(9)	STORM DRAINAGE AND DOWNSPOUT	1.00	Ls	Covers the procurement & installation of downspout at the ROT porch area materials as follows
				PVC Sanitary Pipe, 75mm
				75mm dia Elbow
				PVC Solvent 200cc
				Pre-painted gutter
	/			Down spout pipe cleat / band

Prepared by: KSU INFRA DEPARTMENT

Checked & reviewed by:

Engr. CHRISTIAN JOHE ADORA Chairman for Planning

Engr. RHONUHON R. SARMING Director for Planning Strategy

Arch. Dave D. Ocnat Chairman for Infrastructure

EDUARDO T. BASTANG, CRA, DBM SUC President III